


NOTE:-
1. BACK FILLING TO BE DONE BY HARD MURUM ONLY.
2. PROPER SOIL COMPACTION IN LAYERS TO BE DONE TO ACHIEVE 90% PROCTOR DENSITY TEST.






INDEX PLAN FOR COLUMN & FOOTING

- ALL WALLS ON ALL UPPER FLOORS ARE CONSIDERED OF CONVENTIONAL MATERIAL WITH MAXIMUM DENSITY 1800 kg/m³
- PARTION WALL LOAD CONSIDERED ON RESP.SLABS.
- OUTER WALL THICKNESS IS 150MM & INNER 100 MM THK CONSIDERED

LEGEND

TOILET - 200 MM SUNK



DETAILS OF AST1

NOTES:

- Basic reference code:- IS 456: 2000
- Due care shall be taken to ascertain that requisite strength of concrete is gained before commencement of deshuttering. It shall comply with provisions of Clause No. 11.3 of IS 456: 2000.
- Nominal covers

	Mild	Moderate	Severe
I Footings	50	50	50
II Columns & walls >200mm width (to links of column)	40	40	45
III Columns & walls having width of 200mm & below having reinf. of dia. 16mm & above. (to links of column)	40	40	45
IV Columns & walls having width of 200mm & below having reinf. of dia. 12mm. (to links of column)	25	30	45
V Slabs	20	30	45
VI Beams (to stirrups of beam)	20	30	45
VII Lift wall	40	40	45

- For main reinf. up to 12mm diameter bar for mild exposure, the nominal cover may be reduced by 5mm for slabs & beams only.
- Beams having depth more than 750mm, provide side-face reinforcement.
 - Substratum shall be approved from our office before laying P.C.C.
 - Minimum clear spacing between any two longitudinal bars in beam= 50mm.
 - All laps (Ld) shall be staggered & not more than 50% bars to be lapped at any given section.
- | GRADE OF REINF. | M20 | M25 | M30 | M35 | M40 & ABOVE |
|-----------------|--------|--------|--------|--------|-------------|
| Fe415 | 55 X D | 47 X D | 44 X D | 39 x D | 35 x D |
| Fe500 (TMT) | 66 X D | 56 X D | 53 X D | 46 x D | 42 x D |
- All buildings shall have tie beams/plinth beams at ground/plinth level.
 - If footings overlap each other, necessary revision shall be obtained from our office.
 - Design is valid for number of floors as indicated in the drawing.
 - At any level where column size gets reduced in either dimension tie beams/plinth beams are essential.
 - For cantilevers, top bars to be anchored behind from external face of support for - Ld or span of cantilever - whichever is greater.
 - Fire rating considered:- 2 Hours Max.

Use of this drawing for construction shall explicitly confirm acceptance of following conditions by Owner / Builder / Contractor

- Our responsibility shall remain limited to safe and sound structural design as transmitted by this drawing and we shall not remain responsible for
 - Safety of old structure during demolition.
 - Safety of any adjoining building /persons staying in adjoining building/persons and properties on adjoining roads.
 - Safety of construction worker/any personnel at work site during construction
 - Correctness/safety of any temporary structure, scaffolding, shuttering, centering erected at site and any injury to any personnel arising out of any accidents.
 - Accidents occurring due to premature deshuttering, faulty / substandard construction material or workmanship / faulty construction procedure.
 - Any accident occurring due to construction of elements of buildings not designed by us.
- Supervision if specifically asked for will be provided to the extent of verification of reinforcement on site but responsibility regarding correct & sound construction shall solely rest with contractor/ builder / owner.
- All structural concrete should be weigh batched, machine mixed & mechanically vibrated.
- Any discrepancy between our drawing & Architects' drawing shall be brought to our notice before construction.

NO.	REV. DATE	DESCRIPTION	NO.	REV. DATE	DESCRIPTION
R0	12.04.2021	.	R5	.	.
R1	16.04.2021	.	R6	.	.
R2	.	.	R7	.	.
R3	.	.	R8	.	.
R4	.	.	R9	.	.

DRAWING IS VALID FOR CONSTRUCTION, PROVIDED IT IS SIGNED & STAMPED BY OUR OFFICE

GRADE OF CONCRETE:-		M20	ADVANCE COPY FOR APPROVAL		
GRADE OF STEEL:-		Fe 500 TMT			
ENVIRONMENTAL EXPOSURE CONDITION:-		MODERATE			
DESIGN LIVE LOAD:- (UNLESS SPECIFIED)		200 kg/sq.m			
SUPERIMPOSED DEAD LOAD:-		100 kg/sq.m			
CHECKED BY	DEALT BY	DRAWN BY	DRG. NO.	BLDG:	JOB NO.
-	-	-	-	-	-

DEVELOPER:-	Mr.PRASHANT HARGUDE
ARCHITECT:-	-
PROJECT:-	-
TITLE:-	INDEX PLAN FOR PLINTH BEAMS